2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (300) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a District Forest Office at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing a District Forest Office at Chikmagalur.

No.	Items of work	Per	Quantity
1	Earthwork excavation for foundation and filling in basement	C. yd.	235
2	Concrete in chunam	C. ft.	2,548
3	Burnt stone in chunam	"	5,324
4	Burnt brick in chunam	"	6,159
5	Do archwork	"	853
6	Burnt stone slab dressed 3" to 6"	S. ft.	1,152
7	Plastering with chunam	Sq.	95·14
8	White and colourwashing	"	95·14
9	Pointing with cement	"	8·00
10	Teakwood work wrought and put up including wood oiling	C. ft.	187·74
11	Roofing with 1st class Mangalore tiles with teak reepers to be oiled	Sq.	17·61
12	Roofing with 1st class Mangalore tiles with ceiling tiles, teak reepers with wood oiling.	"	20·87
13	Mangalore ridge tiles set in mortar and pointed with cement	R. ft.	129
14	Mangalore glass tiles	No.	6
15	Teakwood plant, ½" thick for valleys with wood oiling	S. ft.	174
16	Zinc sheets for valleys with chunam borders	"	174
17	Teakwood panelled door with silicate painting	"	312
18	Teakwood panelled windows with iron bars and clamps glazed shutters inside and silicate painting.	"	1234
19	Teakwood flat ventilators with glazed shutters, iron bars, clamps and silicate painting.	"	90
20	Teakwood circular ventilators with glazed shutters, etc., complete	S. ft.	15
21	Teakwood panelled screen with frames, hinges, doorway, oiling	No.	294
22	Cut stone pillars nicely dressed with caps and bases, etc.	Sq.	17
23	Flooring with 9" square Mangalore tiles on 3" concrete bed and cement pointing.	"	10·88
24	Flooring with Cuddappah slabs on 3" concrete bed and cement pointing, etc., complete.	"	9·52
25	Teakwood ornamental eave board with painting	R. ft.	4·58
26	Tarring wood work	L. S.	Rs.
27	Teakwood pendant with painting	No.	22
28	Teakwood finials	"	4
29	Teakwood large board	"	1
30	Sham windows and ventilators in front verandah	L. S.	Rs.
31	Opening out approach road and gravelling and filling in earth in low portions, etc.	"	"
32	Constructing tunnel and clearing site, etc.	"	"
33	Constructing a masonry latrine with a doorway, etc.	"	"
34	Teakwood stands for keeping tents	"	"
35	M. & S. M. Railway purlin	R. ft.	29
	Iron Record Racks.		
1	Iron base for vertical frames with painting	No.	20
2	Angle iron vertical frames do	lbs.	2,585
3	Flat iron bars	"	932
4	Drilling holes and cutting frames, etc.	No.	712
5	Rivets	"	600
6	Teakwood ladder with painting	L. S.	Rs.
7	Sundry works and unforeseen	"	"

K. PONNAPPA,
Executive Engineer.

DISTRICT, MUNICIPAL AND LOCAL BOARDS.

BANGALORE CITY MUNICIPALITY.

Notice dated 8th July 1918.

Sealed tenders for supplying the following articles of furniture will be received by the undersigned in the Municipal Office up to 31st July 1918.

2. Each tender must be accompanied by a deposit of Rs. 25 in cash or in currency notes and be superscribed "Tender for the supply of furniture."

3. Information regarding design, etc., may be had at the Municipal Office, during office hours.

4. The tender must be accompanied by a statement showing the rates at which the different items specified below will be executed.

5. The final acceptance of the tender will rest with the undersigned, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days after the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful tenderer whose tender has been accepted, will be duly notified to him.

8. On acceptence of one or more tenders, the earnest money of rejected tenderers will be returned.

9. The articles should be delivered at the office on or before the end of September 1918.

List of furniture.

Serial No.	Name of furniture		Dimensions	
1	Almirahs	3	4′×6½′×1½′	All these furniture should be made of seasoned Mysore teakwood.
2	Tables with two drawers	18	2½′×4′×2½′	
3	Chairs (Bug proof)	13	Usual size.	
4	Rattan chair	1		
5	Benches	7	6′×1½′×1½′	
6	Stools	7	1½′×1½′×1½′	
7	Pigeon-holes	12	3′×1½′×1½′	
8	Teakwood boxes	12	2′×1½′×1½′	
9	Small racks for keeping registers	6	4′×1½′×1½′	
10	Record rack	2	6′×6′×2½′	
11	Pigeon-hole stand	20	3′×1½′×2′	
12	Chairs for Typists	2	As per sample.	
13	Teapoy	1	2½′×1½′×2′	
14	Folding screen	1	6′×6′	

Notice dated 11th July 1918.

The public are hereby informed that the right of removing manure in the 2nd block of the Division No. II, Bangalore City, during 1918-19, has been leased out to Mr. Nanjunda Sastri instead of to Mr. N. Siddareddi as notified in this Office Notification, dated 24th June 1918, published on page 606, Part IV of the *Mysore Gazette*, dated the 4th July 1918.

Abstract Notification dated 13th July 1918.

The attention of the public is invited to the Notification, dated the 5th July 1918, calling for tenders for the supply of road materials published in pages 619—622, Part IV of the *Mysore Gazette*, dated the 11th July 1918.

The last date for submitting tenders is 27th July 1918.

K. P. PUTTANNA CHETTY,
Honorary President.

TUMKUR DISTRICT.

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 31st July 1918, for restoring Doddamathkur Hunasekatte tank, Register No. 118, Holiyurdurga hobli, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Doddamathkur Hunsekatte tank, Register No. 118, Kunigal Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.